

REGISTERED POST



भा. कृ. अनु. प. –केन्द्रीय शुष्क क्षेत्र अनुसंधान संस्थान
ICAR - Central Arid Zone Research Institute
क्षेत्रीय अनुसंधान स्थान, भुज 370105 / Regional Research Station, Bhuj 370105
Website: www.cazri.res.in, Email: Devi.Dayal@icar.gov.in
Phone No. ...02832-271238 & 271070



No. F. RSB-GEER-Shed/net house/18/ 247

Date:20.9.18

M/S.....

Sub Quotation for Construction of shed/net house under the project Climate Change Adaptation for natural Resource Dependent Communities of Kachchh District – Enhancing Resilience through Water and livelihood security and ecosystem restoration” at RRS, CAZRI, Bhuj.

Dear Sir(s),

You are requested to kindly quote your lowest rates keeping in view the following conditions in respect of the articles indicated overleaf/as per statement enclosed (Schedule to tender).

1. No advance payment will be made. However, the payment is normally made within 30 days from the date of receipt of Bill for execution the work **in good condition as per order.**
2. The quantity proposed in the quotation may be increased or decreased at the discretion of the authority while placing the order.
3. Quotation not found according to specification will be rejected/not considered.
4. The firm should also supply a copy of the authorized dealership certificate of the item, if applicable
5. Quotation should remain valid for 3 months from the date of quotation.
6. No. Form 'C' & 'D' for sales tax will be issued. Payment will be made at full rate, if applicable. However, the firm is required to produce the valid sales tax Registration No. The firm should also indicate PAN/TIN as per Income Tax Rules.
7. The Rates **should be clearly indicated in figure as well as in words.** While quoting the rates, it may be clearly indicated whether the items are inclusive or exclusive of ST, CST etc. in terms of percentage or in absolute term.
8. Works will have to be completed normally within 30 days from the date of issue of work order or as mentioned in the supply order unless such extension is allowed by the Institute **failing which suitable penalty as indicated in the work order will be imposed.**
9. Director, CAZRI, Jodhpur reserves the right to accept or reject any or all the quotation without assigning any reason.
10. The firm may also visit for inspection and on site assessment before submitting quotations.
11. All bids must be accompanied by a bid security / **EMD of Rs. nil**-of the estimated value of the cost, in the form of a Demand Draft of a scheduled commercial bank in India, in favour of **ICAR Unit-CAZRI, Jodhpur.** Without EMD quotation will not be considered.
12. The firm awarded the contract may/will have to furnish a performance security in the form of Bank Guarantee as per the proforma to be supplied along with work order or FDR pledged to "ICAR Unit - CAZRI, Jodhpur" from a scheduled Commercial Banks for an amount which may vary from 5% to 10% of the value of the contract at the discretion of Director, which should remain valid for six months.
- 13..The quotation may be sent to the office by courier/Registered Post/Speed Post in sealed cover super scribed with **for shed/net house under the project of Climate Change Adaptation for natural Resource Dependent Communities of Kachchh District at RRS, CAZRI, Bhuj.**
14. The quotation must be reached to this Office on or before **4.10.18 at 3.00 PM** which it will not be considered. The quotation should be dropped in the Tender Box placed in the ICAR-CAZRI, RRS, Kukma, Bhuj.

Yours faithfully,

20/9/18



भा. कृ. अनु. प. – केन्द्रीय शुष्क क्षेत्र अनुसंधान संस्थान
ICAR - Central Arid Zone Research Institute
क्षेत्रीय अनुसंधान स्थात्र, भुज 370105 / Regional Research Station, Bhuj 370105
Website: www.cazri.res.in, Email: Devi.Dayal@icar.gov.in
Phone No.02832-271238 & 271070



No. F. RSB-GEER-Shed/net house/18/

Date:20.9.18

निविदाप्रपत्र

(इस फार्म को निविदा प्रपत्र के साथ जमा कराना आवश्यक है)

निदेशक, केन्द्रीय शुष्क क्षेत्र अनुसंधान संस्थान, क्षेत्रीय अनुसंधान स्थात्र, भुज 370105 निम्नलिखित कार्य के लिए सीमित मोहरबन्द निविदाये आमंत्रित करते हैं।

1. कार्य का नाम : Shed/net house under the project of Climate Change Adaptation for natural Resource Dependent Communities of Kachchh District – Enhancing Resilience through Water and livelihood Security and ecosystem restoration, at RRS, CAZRI, Bhuj.
2. निविदादाता फर्म कानाम/पूर्ण पता :
3. टेलीफोन/माबोईल नम्बर :
4. निविदादाता फर्म का : PAN No.
:TIN No.
5. बैंक का विवरण : बैंक का नाम.....
: पता
6. निविदा प्रपत्र की कीमत : रु. शून्य
7. धरोहर (बयाना) राशि : रु. शून्य
8. कार्य पूर्ण करने की अवधि : एक माह
9. निविदा जमा कराने की अतिम तिथि : **4.10.18 at 3.00 PM**
10. निविदा कार्य की विस्तृत सूचना काजरी की वबेसाईट <http://www.cazri.res.in> पर देखी जा सकती है।
11. निविदा प्रपत्र काजरी, जोधपुर की वबेसाईट से भी डाउनलाडे किये जा सकते है।

निविदादाता के मोहर सहित हस्ताक्षर

NAME OF WORK :- Estimate for Construction of Shed /Net house under the project of "Climate Change Adaptation for natural Resource Dependent Communities of Kachchh District, at RRS, Bhuj.

Sr.no	Description	Quantity	Unit	Rate/Unit	Amount(Rs.)
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth, 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50m and lift up to 1.5m, disposed earth to be levelled and neatly dressed.				
	All kinds of soil	1.25	cum		
2	CEMENT PLASTER				
	20 mm cement plaster of mix :				
	1:6 (1 cement: 6 coarse sand)	1	Sqm		
3	CEMENT CONCRETE (CAST – IN-SITU)				
	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
	1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)	0.75	cum		
4	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20mm nominal size) upto plinth level with :				
	Cement mortar 1:6 (1 cement : 6 coarse sand).	0.75	cum		
5	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete.				
	40mm thick with 20mm nominal size stone aggregate.	8	sqm		
6	STEEL WORK				

	Providing and fixing hand rail of approved size by welding etc. to steel ladder railing, balcony railing, staircase railing and similar works, including applying priming coat of approved steel primer.				
	G.I. pipes	300	Kg.		
7	Dom shaped Net House Size:- 16m Long X8m Wide x 4.5m High from centre Cladding Material :- UV Stabilized 50% Agro -shading,, Net fixing with wiring and profile. Floor with natural soil,Fibre sheet Door (Size- 2.10mx 1m) with Locking arrangement and frame made with angle iron with colour and primer.	1	LS		
				Total	

Signature with seal of tenderer