

REGISTERED POST

INDIAN COUNCIL OF AGRICULTURAL RESEARCH  
CENTRAL ARID ZONE RESEARCH INSTITUTE, JODHPUR  
Telephone and FAX : 0291-2786485

No.F. 8 (2) /11-12/ Reno.M.Gate /Adm-V  
To,

Dated:-

M/S.....

.....

.....

JODHPUR.

**Sub:** Quotation for Renovation of Main Gate of CAZRI, Jodhpur.

Dear Sir(s),

You are requested to kindly quote your lowest rates keeping in view the following conditions in respect of the articles indicated overleaf/as per statement enclosed (Schedule to tender).

1. No advance payment will be made. However, the payment is normally made within 30 days from the date of receipt of Bill for execution the work **in good condition as per order**.
2. The quantity proposed in the quotation may be increased or decreased at the discretion of the authority while placing the order.
3. Quotation not found according to specification will be rejected/not considered.
4. The firm should also supply a copy of the authorized dealership certificate of the item, if applicable
5. Quotation should remain valid for 3 months from the date of quotation.
6. No. Form 'C' & 'D' for sales tax will be issued. Payment will be made at full rate, if applicable. However, the firm is required to produce the valid sales tax Registration No. The firm should also indicate PAN/TIN as per Income Tax Rules.
7. The Rates **should be clearly indicated in figure as well as in words**. While quoting the rates, it may be clearly indicated whether the items are inclusive or exclusive of ST, CST etc. in terms of percentage or in absolute term.
8. Works will have to be completed normally within 30 days from the date of issue of work order or as mentioned in the supply order unless such extension is allowed by the Institute **failing which suitable penalty as indicated in the work order will be imposed**.
9. Director, CAZRI, Jodhpur reserves the right to accept or reject any or all the quotation without assigning any reason.
10. All bids must be accompanied by a bid security / **EMD of Rs. 8000/-** of the estimated value of the cost, in the form of a Demand Draft on a scheduled commercial bank in India, in favour of **ICAR Unit-CAZRI, Jodhpur**. Without EMD quotation will not be considered.
11. The firm awarded the contract may/will have to furnish a performance security in the form of Bank Guarantee as per the proforma to be supplied along with work order or FDR pledged to "**ICAR Unit - CAZRI, Jodhpur**" from a scheduled Commercial Banks or it may be deducted from bills for an amount which may vary from 5% to 10% of the value of the contract at the discretion of Director, which should remain valid for six months.
12. The quotation may be sent to the office by courier/Registered Post/Speed Post in sealed cover super scribed with "**Renovation of Main Gate**" **Due date 14-02-2012**.
13. **The quotation** must be reached to this Office on or before **14-02-2012 up to 3.00 PM** failing which it will not be considered. The quotation should be dropped in the Tender Box placed in the Adm.V Section..

Yours faithfully,

ASSISTANT ADMINISTRATIVE OFFICER (ADM.V)

**Name of Work: Renovation of Main Gate, CAZRI, Jodhpur.**

S. No	Particular of work	Quantity	Rate (s)	Amount(Rs.)
1.	Supplying and fixing 22 cm. thick white Ashlar bad (pillar cap) 45 cm wide X 135 cm long (3 line dressed) all exposed, side complete including cutting, moulding and chaffering etc.	6 Nos.	@..... Each.	.....
2.	Demolishing lime concrete and disposal of material within 50 meter lead as per direction of Engg. Incharge.	12.60 cum.	@..... Cum	.....
3.	Providing and laying in position cement concrete including curing compaction etc. of specified grade excluding the cost of centering and shuttering. All up to plinth level.			
(i)	1: 2 : 4 (1 Cement : 2 Course Sand : 4 Graded stone aggregate 20 mm nominal size)	8.08 cum.	@..... Cum	.....
(ii)	1: 4 : 8 (1 Cement : 4 Course Sand : 8 Graded stone aggregate 40 mm nominal size.	27.56 cum.	@..... Cum	.....
4.	Supplying and fixing 13 cm. Thick white Ashlar bad (pillar cap) 60X60 Cm (3 line dressed) all exposed side complete including cutting, moulding and chaffering etc.	4 Nos.	@..... No.	.....
5.	Earth work in surface excavation not exceeding 30 Cm. in depth but exceeding 1.5 meter in width as well as 10 Sqm on plan including disposal of excavated earth up to 50Mtr. and lift up to 1.5 Mtr. disposed soil to be leveled and neatly dressed: All kinds of soil.	183.75 Sqm	@..... Sqm.	.....
6.	Providing & laying plished vitrified floor tiles in difference sizes (thickness to be specified by the manufacturer) with water absorption's less than 0.08% and conforming to IS:15622 of approved make in all colours and shades, laid on 20 mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete. Size of Tile 50 x 50 cm	84.00 Sqm	@..... Sqm.	.....
7	Finishing wall with Acrylic Smooth exterior paint of required shade: Old work (Two or more coat applied @ 1.67 Ltr./10 sqm.) on existing cement paint surface).	550.00 Sqm	@..... Sqm.	.....
8	Providing and fixing Interlocking cement concrete block (pauer block) including laying/leveling the bad surface of coarse sand 25 to 50 mm thick.	183.75 Sqm	@..... Sqm	.....
9	Removing dry or oil bound distemper, water proofing cement pain and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	64 Sqm.	@..... Sqm	.....
9	Distempering with oil bound washable distempering of approved brand and manufacture to give an even shade. Old work (one or more coats)	64.00 Sqm	@..... Sqm	.....
10	Painting with synthetic enamel paint of approved brand and manufacture or required colour to give an even shade: One or more coats on old work.	60.00 Sqm	@..... Sqm	.....

PAN NO. ....

TIN No. ....

Signature with seal of tenderer

INDIAN COUNCIL OF AGRICULTURAL RESEARCH  
CENTRAL ARID ZONE RESEARCH INSTITUTE, JODHPUR

No.F. 29-36/Cont. of Plat. at Feed Tech Unit, Ju/10/AdmII

Dated:-

To,

M/S.....

.....

.....

JODHPUR.

**Sub:** Quotation for construction of platform at feed technology unit, CAZRI, Jodhpur.

Dear Sir(s),

You are requested to kindly quote your lowest rates keeping in view the following conditions in respect of the articles indicated overleaf/as per statement enclosed (Schedule to Tender).

1. No advance payment will be made. However, the payment is normally made within 30 days from the date of receipt of Bill for execution the work **in good condition as per order**.
2. The quantity proposed in the quotation may be increased or decreased at the discretion of the authority while placing the order.
3. Quotation not found according to specification will be rejected/not considered.
4. The firm should also supply a copy of the authorized dealership certificate of the item, if applicable
5. Quotation should remain valid for 3 months from the date of quotation.
6. No. Form 'C' & 'D' for sales tax will be issued. Payment will be made at full rate, if applicable. However, the firm is required to produce the valid sales tax Registration No. The firm should also indicate PAN/TIN as per Income Tax Rules.
7. The Rates **should be clearly indicated in figure as well as in words**. While quoting the rates, it may be clearly indicated whether the items are inclusive or exclusive of ST, CST etc. in terms of percentage or in absolute term.
8. Works will have to be completed normally within 30 days from the date of issue of work order or as mentioned in the supply order unless such extension is allowed by the Institute **failing which suitable penalty as indicated in the work order will be imposed**.
9. Director, CAZRI, Jodhpur reserves the right to accept or reject any or all the quotation without assigning any reason.
10. All bids must be accompanied by a bid security / **EMD of Rs. 10,000/-** of the estimated value of the cost, in the form of a Demand Draft on a scheduled commercial bank in India, in favour of **ICAR Unit-CAZRI, Jodhpur**. Without EMD quotation will not be considered.
11. The firm awarded the contract may/will have to furnish a performance security in the form of Bank Guarantee as per the proforma to be supplied along with work order or FDR pledged to **"ICAR Unit - CAZRI, Jodhpur"** from a scheduled Commercial Banks or it may be deducted from bills for an amount which may vary from 5% to 10% of the value of the contract at the discretion of Director, which should remain valid for six months.
12. The quotation may be sent to the office by courier/Registered Post/Speed Post in sealed cover super scribed with **3 Phase EC Lab.9 CAZRI, Jodhpur " Due date 14/02/2012**.
13. **The quotation** must be reached to this Office on or before **14/02/2012 up to 3:00 PM** failing which it will not be considered. The quotation should be dropped in the Tender Box placed in the Adm.V Section with AAO.

Yours faithfully,

ASSISTANT ADMINISTRATIVE OFFICER (ADM.V)

**Name of work : Construction of platform at feed technology unit, CAZRI, Jodhpur.**

S.No.	Particular of work	Quantity	Rate to be quoted	Amount (Rs.)
1.	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m. All kinds of soil.	33.39 Cum.	@..... Cum.	.....
2	Supplying and filling in plinth with river sand under floors including, watering, remming consolidating and dressing complete.	90.56 Cum	@..... Cum.	.....
	Stone work, plain in copings, cornices, string courses and plinth courses, upto 75mm thick in Cement mortar 1:6 (1 Cement : 6 coarse sand) including pointing with white cement mortar 1:2 (1 white Cement : 2 stone dust) with an admixture of pigment. White sand stone	1.65 Cum	@..... Cum.	.....
3.	<b>CEMENT CONCRETE (CAST-IN-SITU)</b>			
4.	P & L in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 Cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size )	51.95 Cum	@..... Cum.	.....
5.	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 Cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size ) at plinth level with: Cement mortar 1:6 (1 cement : 6 coarse sand)	25 Cum	@..... Cum.	.....
6.	Cement concrete pavement with 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size ) including finishing complete.	25 Cum	@..... Cum.	.....
7.	<b>CEMENT PLASTER (IN COARSE SAND)</b>			
	20 mm cement plaster of mix : 1:6 (1 cement : 6 coarse sand)	33.44 Cum	@..... Cum.	.....

PAN NO. ....

TIN No. ....

Signature with seal of tenderer