

**REGISTERED POST**

**CENTRAL ARID ZONE RESEARCH INSTITUTE**  
(INDIAN COUNCIL OF AGRICULTURAL RESEARCH)  
**Jodhpur (Raj.)-342 003, Phone/Fax-0291-2786485**

F. No. 9 (9) Canal-TSP, Bernia/13-14/Adm-V

Dated: 04/12/2013

To,

M/s.....  
.....  
.....

Sub: Construction of Canal of 400m length at Bernia Watershed (Dungarpur).

Dear Sir(s),

You are requested to kindly quote your lowest rates keeping in view the following conditions in respect of the articles indicated overleaf/as per statement enclosed (Schedule to tender).

1. No advance payment will be made. However, the payment is normally made within 30 days from the date of receipt of Bill for execution the work **in good condition as per order**.
2. The quantity proposed in the quotation may be increased or decreased at the discretion of the authority while placing the order.
3. Quotation not found according to specification will be rejected/not considered.
4. The firm should also supply a copy of the authorized dealership certificate of the item, if applicable
5. Quotation should remain valid for 3 months from the date of quotation.
6. No. Form 'C' & 'D' for sales tax will be issued. Payment will be made at full rate, if applicable. However, the firm is required to produce the valid sales tax Registration No. The firm should also indicate PAN/TIN as per Income Tax Rules.
7. The Rates **should be clearly indicated in figure as well as in words**. While quoting the rates, it may be clearly indicated whether the items are inclusive or exclusive of ST, CST etc. in terms of percentage or in absolute term.
8. Works will have to be completed within stipulated period as per work order **failing which suitable penalty as indicated in the work order will be imposed**.
9. Director, CAZRI, Jodhpur reserves the right to accept or reject any or all the quotation without assigning anyreason.
10. All bids must be accompanied by a bid security/**EMD of Rs. 8500** /- of the estimated value of the cost, in the form of a Demand Draft of a scheduled commercial bank in India, in favour of **ICAR Unit - CAZRI, Jodhpur**. Without EMD quotation will not be considered.
11. The firm awarded the contract may/will have to furnish a performance security in the form of Bank Guarantee as per the proforma to be supplied along with work order or FDR pledged to "**ICAR Unit - CAZRI, Jodhpur**" from a scheduled Commercial Banks or it may be deducted from bills for an amount which may vary from 5% to 10% of the value of the contract at the discretion of Director, which should remain valid for six months.
12. The quotation may be sent to the office by courier/Registered Post/Speed Post in sealed cover super scribed with "**Construction of Canal at Bernia Watershed (Dungarpur)**." **Due date 27/12/2013**.
13. **The quotation** must be reached to this Office on or before **27/12/2013 up to 3.00 PM** failing which it will not be considered. The quotation should be dropped in the Tender Box placed in the Adm.V .

Yours faithfully,

ASSISTANT ADMINISTRATIVE OFFICER (ADM.V)

Name of Work: Construction of Canal of 400m length at Bernia Watershed (Dungarpur).

No.	Description	Quantity	Rate	Amount (Rs.)
1.	Cutting and clearance of jungle bushes, shrubs Ankra/Ipomonea, Juliflora types etc. on canal and bunds in dry/moist/slushy conditions including disposal as per instruction of Engineer incharge. Cost of woods has been deducted from rates and thus will be property of contactor after cutting ordinary. (1 x 0.9)	0.9 x 400 = <b>360 Sqm</b>	@...../ Sqm	.....
2.	Excavation including loading, unloading, disposal and dressing of excavated earth within initial lead of 50m and lift up to 1.5m in dry or moist including dressing of excavated area, dewatering wherever required complete in all respect. (1 x 0.9 x 0.2). Hard soil mixed with kankar/boulders, murrum.	0.18 x 400 = <b>72 Cum</b>	@...../ Cum	.....
3.	Cement concrete (1:3:6) M-10 well mixed and laid in position complete including all leads of all construction materials including curing and finishing having well graded crusher broken stone aggregates of maximum size up to 40 mm. (1 x 0.9 x 0.15)	0.135 x 400 = <b>54 Cum</b>	@...../ Cum	.....
4.	Random rubble stone masonry (using R.R. stones where 75% stones to be not less than 15 cm in size in any direction and weighing not less than 23 kg) for super structure including curing all leads of all construction materials including curing etc. complete cement sand mortar (1:6). Thickness of wall up to 30 cm. (1 x 2 x 0.3 x 0.3)	0.18 x 400 = <b>72 Cum</b>	@...../ Cum	.....
5.	Plaster in cement sand mortar (1:3) including raking of joints smooth finishing and curing etc. complete including all leads of all construction materials of thickness of 20 mm. (1 x 2 x 0.3) + (1 x 2 x 0.25)	1.10 x 400 = <b>440 Sqm</b>	@...../ Sqm	.....
6.	Providing and laying cement concrete coping in 1:2:4 with mix size of crusher broken aggregates up to 20 mm including shuttering etc. with all leads of material complete in all respect in thickness 50 mm (1 x 0.3 + 2 x 0.3)	0.9 x 400 = <b>360 Sqm</b>	@...../ Sqm	.....
Total in figures :				
Total in words :				

PAN NO. ....

TIN No. ....

Signature with of tenderer