



Central Arid Zone Research Institute
(Indian Council of Agricultural Research)
Jodhpur-342 003, Phone/Fax No. 0291-2786485



F. No. 10 (2) Germplasm Unit/12-13/Adm.V

Dated: **7-01-2014**

TENDER NOTICE

On behalf of the Project Investigator, Field Gene Bank for Arid Region and NICRA Project of Director, CAZRI, Jodhpur sealed tenders are invited on **due date 28.01.2014 at 2.30 PM** for following civil works from registered firm/agency of repute having PAN and experience of minimum two years in Govt. Establishments/CPWD/PWD. The interested agency/firm may purchase the tender form from the Institute on any working day from 9-01-2014 to 27-01-2014 by paying tender fee a sum of Rs. 500/- (non-refundable) for each work either in cash or by Bank Draft in favour of ICAR UNIT-CAZRI, Jodhpur. The tender documents completed in all respect along with Earnest Money should be submitted to this office **on or before Due Date**. The Principal Investigator reserves rights to accept or reject any tender without giving any reasons. Tenders without earnest money will be out rightly rejected. The tender form available at website **www.cazri.res.in** which may be downloaded and submitted to this office with tender fee.

No.	Name of work	Estimate (Rs.)	EMD (Rs.)	Tender fee (Rs.)	Tender opening date
1.	C/o Germplasm processing unit for FGBP	9,94,118/-	20,000/-	500/-	28.01.2014 at 3.00 PM
2.	C/o Water Storage Tank for FGBP	4,89,300/-	10,000/-	500/-	
3.	Chain Link fencing for FGBP	10,00,000/-	20,000/-	500/-	
4.	Chain Link for NICRA	4,92,132/-	10,000/-	500/-	

ASSTT. ADMINISTRATIVE OFFICER (V)



केन्द्रीय शुष्क क्षेत्र अनुसंधान संस्थान
(भारतीय कृषि अनुसंधान परिषद)
जोधपुर-342003, फोन/फैक्स नं. 0291.2786485



F.No. 10 (2) Germ Plasm Unit/12-13/Adm V

Dated:-

निविदा प्रपत्र

भारत संघ के राष्ट्रपति एवं उनकी ओर से निदेशक /प्रोजेक्ट इनवेस्टीगेटर, केन्द्रीय शुष्क क्षेत्र अनुसंधान संस्थान, जोधपुर निम्नलिखित कार्य के लिए खुली मोहरबन्द निविदाये आमंत्रित करते है ।

1. निविदादाता फर्म का नाम व पूर्ण पता : _____
2. टेलिफोन/मोबाइल नम्बर : _____
E.mail ID : _____
3. निविदादाता फर्म का : PAN No.
TIN No.....
4. कार्य का नाम : Construction of Germplasm procssing & storage
facility Unit at CAZRI, Jodhpur.
5. कार्य की अनुमानित लागत : **रु. 9,94,118/- Based on DSR, 2012 of CPWD**
6. धरोहर (बयाना) राशि : **रु. 20000.00 in favour of ICAR Unit CAZRI,
Jodhpur**
7. कार्य पूर्ण करने की अवधि : **1 माह**
8. निविदा प्रपत्र की कीमत : **रु. 500/-**
9. निविदा प्रपत्र बेचने की अंतिम दिनांक : **27-01-2014** को अपरान्ह 4.00 बजे तक
10. निविदा प्रपत्र जमा करने की अंतिम दिनांक : **28-01-2014** को अपरान्ह 2.30 बजे तक
11. निविदा खुलने की दिनांक : **28-01-2014**को अपरान्ह 3.00 बजे तक
12. यह निविदा सूचना संख्या दिनांक **7-01-2014** का संक्षिप्त विवरण है तथा उपरोक्त निविदाओ की विस्तृत निविदा सूचना काजरी, जोधपुर की बेवसाईट <http://www.cazri.res.in> पर देखी जा सकती है।
13. निविदा प्रपत्र दिनांक **9-01-2014** और उसके बाद काजरी, जोधपुर की बेवसाईट <http://www.cazri.res.in> से भी डाउनलोड किये जा सकते है । डाउनलोड किये गये निविदा प्रपत्र की कीमत रु. 500/- का डिमाण्ड डाफ्ट /पे आर्डर जो कि **ICAR Unit-CAZRI, Jodhpur** के पक्ष में देय हो निविदा प्रपत्र के साथ संलग्न करनी होगी अन्यथा निविदा को सरसरी तौर पर रद्द कर दी जायेगी ।

सहायक प्रशासकीय अधिकारी (पंचम)

निविदा के नियम व शर्तें:-

1. निविदा प्रपत्र संस्थान के अनुभाग-पंचम् द्वारा बेचे जायेंगे। निविदा प्रपत्र संस्थान के सहायक प्रशासकीय अधिकारी (पंचम्) से कार्यालय समय के दौरान किसी भी कार्य दिवस को कैशियर के पास निविदा प्रपत्र शुल्क नकद जमा कर प्राप्त की जा सकती है। काजरी की वेबसाईट ली गयी निविदा पत्र के साथ निविदा शुल्क रु. 500/- राष्ट्रीयकृत बैंक द्वारा जारी डिमाण्ड ड्राफ्ट/पे ऑर्डर के रूप में जो कि **ICAR Unit-CAZRI, Jodhpur** के नाम देय होना चाहिए जो 90 दिन तक वैध हो।
2. जिन निविदाओं के साथ आवश्यक धरोहर (बयाना) राशि नहीं होगी, उन्हें सरसरी तौर पर रद्द कर दिया जायेगा। बैंक गारन्टी को धरोहर राशि के लिए स्वीकार नहीं किया जायेगा। धरोहर राशि (बयाना) भारतीय स्टेट बैंक या किसी राष्ट्रीयकृत बैंक द्वारा जारी डिमाण्ड ड्राफ्ट/पे ऑर्डर के रूप में जो कि **ICAR Unit-CAZRI, Jodhpur** के नाम देय होना चाहिए जो 90 दिन तक वैध हो।
3. निविदा पूर्ण रूप से भरी हुई मोहरबन्द लिफाफे, जिस पर मोटे अक्षरों में निविदा कार्य का नाम “**C/o Germplasm procssing Unit under FGBAR at CAZRI, Jodhpur**” लिखा हो, में निविदा प्रपत्र के साथ आवश्यक कागजात के साथ सहायक प्रशासकीय अधिकारी (पंचम्) के कार्यालय में रखे टेण्डर बॉक्स में जमा करानी होगी। निर्धारित दिनांक एवं समय के पश्चात् डाक द्वारा देशी से प्राप्त निविदाओं को स्वीकार नहीं किया जायेगा। निविदा उसी दिन अपरान्ह 3.00 बजे खोली जायेगी। निविदा प्रपत्र की कीमत न तो वापस की जा सकती है और न ही स्थानान्तरित की जा सकती है।
4. निविदा निर्धारित प्रोफोर्मा में प्रस्तुत न करने पर निविदा निरस्त समझी जायेगी।
5. निविदा में दर अंको और शब्दों में स्पष्ट अंकित करें। निविदा में प्रस्तुत दर में व्याणिज्य कर, सेवाकर या अन्य कर दर में शामिल या अलग है, स्पष्ट उल्लेख करें।
6. निविदा में मदवार (**Item wise**) दर प्रस्तुत न करने पर निविदा निरस्त कर दी जाएगी।
7. आदेश जारी करते समय निविदा में अंकित मात्रा बढ़ाई या घटाई जा सकती है।
8. निविदा प्रस्तुत करने की तिथि से 6 माह तक वैध रहेगी।
9. कार्य आदेश प्रस्तुत होने के 1 माह के अन्दर कार्य पूर्ण करना होगा अन्यथा समयावधि बढ़ाने की अनुमति मांगी जाय जो कि प्रदान कर दी जायेगी।
10. सफल निविदादाता को कार्य आदेश की कीमत का 10 प्रतिशत परफार्मेंस गारंटी (सुरक्षा राशि) राशि कार्य प्रारंभ करने से पूर्व जमा करना होगा। विशेष परिस्थिति में ठेकेदार फर्म द्वारा लिखित प्रार्थना प्रस्तुत करने पर यह राशि कार्य के बिल से काटी जा सकती है और धरोहर राशि सुरक्षा राशि में समायोजित की सकती है। कार्य पूर्ण होने की तिथि के 6 माह बाद सुरक्षा राशि प्रार्थना प्रस्तुत करने पर लौटाई जायेगी जिस पर ब्याज देय नहीं होगा।
11. कार्य का कोई अग्रिम भुगतान नहीं किया जायेगा। सामान्य तौर पर कार्य पूर्ण करने पर बिल प्रस्तुति की तिथि से 30 दिन के अंदर भुगतान कर दिया जाता है।
12. पात्रता मानदण्ड : -
केवल ऐसे निविदादाता/फर्म को आवेदन करने की जरूरत है, जो निम्नलिखित पात्रता मानदण्ड को पूर्ण करें :
(क) निविदादाता फर्म केन्द्रीय लोक निर्माण विभाग, एम.ई.एस., काजरी, राजस्थान सरकार के सार्वजनिक लोक निर्माण विभाग, जे.डी.ए., नगर निगम, या किसी सरकारी विभाग में निर्माण एवं विद्युत कार्य के लिए पंजीकृत होनी चाहिए। पंजीयन प्रमाण पत्र की प्रतिलिपि प्रस्तुत करनी होगी।
(ख) समान प्रकृति का कार्य का अनुभव :- निविदादाता द्वारा विगत दो वित्तीय वर्षों (अर्थात् 2011-2012 एवं 2012-13) एवं चालू वित्तीय वर्ष निविदा खुलने की तिथि तक, कम से कम एक समान प्रकृति का कार्य जो निविदा सूचना में दर्शाई गई कार्य की अनुमानित लागत का कम से कम 35 प्रतिशत हो, किसी सरकारी विभाग, अर्द्ध-सरकारी, ऑटोनोमस बोडी, रेग्युलेट निजी प्रतिष्ठान में पूर्ण होना चाहिए।
(ग) निविदा पत्र के **Annexaure-I** में दर्शाये गये दस्तावेजों के प्रूफ/प्रतिलिपि निविदा के साथ प्रस्तुत करने होंगे।

13. निविदा प्रस्तुत करने से पहले कार्य का **Drawing**, यह निविदा प्रपत्र के साथ संलग्न है, का अवलोकन करलें।
14. निविदादाता को विधि/लीगल स्टेटस/पार्टनरशिप फर्म इत्यादि से संबंधित सभी कागजात निविदा प्रपत्र के साथ प्रस्तुत करने होंगे। निविदा खुलने के पश्चात निविदादाता फर्म के स्टेटस से संबंधित कोई भी दस्तावेज मान्य नहीं होगा।
15. निविदा प्रपत्र प्रस्तुत करने के लिए, निविदा प्रपत्र केन्द्रीय शुष्क अनुसंधान संस्थान, जोधपुर की वेबसाइट <http://www.cazri.res.in> से भी डाउनलोड किये जा सकते हैं और डाउनलोड किये गये निविदा प्रपत्र की कीमत का डिमाण्ड ड्राफ्ट/पे-ऑर्डर के रूप में **ICAR Unit-CAZRI, Jodhpur** के पक्ष में देय निविदा प्रपत्र के साथ प्रस्तुत करनी होगी अन्यथा इसके बिना निविदा सरसरी तौर पर निरस्त कर दी जायेगी।
16. निविदा प्रपत्र में उल्लेखित तारीख, समय, नियम व शर्तों में किसी भी प्रकार के परिवर्तन यदि हो तो निविदा खुलने के पूर्व निर्धारित वेबसाइट पर सूचना डाल दी जायेगी, जिसे वेबसाइट पर देखा जा सकता है। देय तिथि का अवकाश होने पर अगले कार्य दिवस में निविदाएं निर्धारित समय पर खोली जायेगी।
17. कार्य में प्रयुक्त श्रमिक एवं कार्मिकों का भुगतान के ठेकेदार फर्म स्वयं जिम्मेवार होगी। उनके कल्याण मद जैसे— ई.पी.एफ., ई.एस.आई., कार्य के दौरान दुर्घटना, मृत्यु आदि जोखिम के लिए पूर्ण रूप से ठेकेदार फर्म जिम्मेवार होगी।
18. किसी भी प्रकार के विवाद की स्थिति में न्यायिक क्षेत्र जोधपुर होगा।
19. निविदा को बिना कारण बताये स्वीकृत अथवा अस्वीकृति करने का निदेशक, काजरी, जोधपुर को पूर्ण अधिकार है।

सहायक प्रशासकीय अधिकारी (पंचम)

CHECKLIST OF DOCUMENTS SUBMITTED

SN	Documents to be submitted	Submitted	Not Submitted	Remarks
1.	Details of EMD deposited			
2.	Details of Cost of bidding document			
3.	Copy of Registration of firms			
4.	Copy of Income Tax Return for last 2 years.			
5.	Copy of Service Tax Number if applicable			
6.	Copy of PAN/TIN Card			
7.	List of clients indicating quantum of work executed with them			
8.	Proof of experience			
9.	Last 2 years audited statement from Chartered Accountant.			

Detail of the experience /work done minimum 2 years

S. No.	Name of Client Deptt. / Organisation & Name of Contact person with Ph. No.	<u>Period</u>		Remarks
		From	To	
1.				
2.				
3.				

Signature with seal of Bidder

Name of Work: **Construction of Germplasm processing & storage facility Unit at**
CAZRI, Jodhpur.

No.	Particular of work	Quantity	Rate be quoted	Amount (Rs.)
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. : All kinds of soil.	54.72 cum	@...../Cum
	CEMENT CONCRETE (CAST - IN - SITU)			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:			
(i)	1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size).	13.68 cum	@...../Cum
(ii)	1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)	23.28 cum	@...../Cum
3	Random rubble masonry with hard stone in foundation and plinth including leveling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20mm nominal size) at plinth level with : Cement mortar 1:6 (1 cement : 6 coarse sand)	26.22 cum	@...../Cum
4	Coursed rubble masonry (second sort) with hard stone in foundation & plinth with : Cement mortar 1:6 (1 cement : 6 coarse sand)	45 cum	@...../Cum
5	Extra for coursed rubble masonry with hard stone (first or second sort) in superstructure above plinth level and upto floor five level :	45 cum	@...../Cum
6	CAST-IN-SITU			
	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level - 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	15.32 cum	@...../Cum
7	FORM WORK			
	Centering and shuttering including strutting, propping etc. and removal of form for :			
(I)	Suspended floors, roofs, landings, balconies and access platform.	66.3 sqm	@...../Sqm
(II)	Lintels, beams, plinth beams, girders, bressumers and cantilevers.	35.82 sqm	@...../Sqm
8	STEEL REINFORCEMENT			
	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete : Hot rolled deformed bars	1600 kg	@...../Kg

No.	Particular of work	Quantity	Rate be quoted	Amount (Rs.)
9	KOTA STONE FLOORING			
(i)	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm thick.	60 sqm	@...../Sqm
(ii)	Kota stone slabs 25 mm thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete.	25 sqm	@...../Sqm
10	POINTING ON STONE WORK			
	Pointing on stone work with cement mortar 1:3 (1 cement: 3 fine sand): Flush/ Ruled pointing	136 sqm	@...../Sqm
11	CEMENT PLASTER (IN COARSE SAND)			
	20 mm cement plaster of mix : 1:6 (1 cement: 6 coarse sand)	290 sqm	@...../Sqm
12	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete : 40mm thick with 20mm nominal size stone aggregate.	87.7 sqm	@...../Sqm
13	Providing and fixing T-iron frames for doors, windows and ventilators of mild steel Tee-sections, joints mitred and welded with 15x3 mm lugs 10cm long embedded in cement concrete blocks 15x10x10 cm of 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) or with wooden plugs and screws or rawl plugs and screws or with dash fastener or with fixing clips or with bolts and nuts as require including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer.	225 kg	@...../Kg
14	Providing and fixing factory made ISI marked steel glazed doors, windows and ventilators side /top /centre hung with beading and all members such as K11 B and K12 B etc. complete of standard rolled steel sections, joints mitred and flash butt welded and sash bars tenoned and riveted with 15x3mm lugs, 10cm long, embedded in cement concrete blocks 15x10x10cm of 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size) or with wooden plugs and screws or rawl plugs and screws or with fixing clips or with bolts and nuts as required, including providing and fixing of hinges, pivots, float glass panes with glazing clips and special metal sash putty of approved make and a priming coat of approved steel primer excluding the cost of metal beading and other fittings except necessary hinges or pivots complete as per approved design.	100 kg	@...../Kg

No.	Particular of work	Quantity	Rate be quoted	Amount (Rs.)
15	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required : In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	225 kg	@...../Kg
16	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows including ISI marked black enamelled M.S butt hinges with necessary screws excluding, panelling which will be paid for separately : Second class teak wood. 35 mm thick shutters	8 sqm	@...../Sqm
	INTERIOR FINISHING			
17	White washing with lime to give an even shade : New work (three or more coats)	60 sqm	@...../Sqm
18	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : New work (two or more coats) over and including priming coat with cement primer.	175 sqm	@...../Sqm
	EXTERIOR FINISHING			
19	Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm).	60 sqm	@...../Sqm
20	Applying priming coat : With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood)	40 sqm	@...../Sqm
21	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture.	40 sqm	@...../Sqm
22	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete : 100 mm dia. R.C.C. pipe	10 metre	@...../Meter
Grand Total (in figures)				
(In words)				

Signature with seal of tenderer