

#### भा. कृ. अनु. प. — केन्द्रीय शुष्क क्षेत्र अनुसंधान संस्थान ICAR - Central Arid Zone Research Institute जोधपुर (राजस्थान) 342 003/Jodhpur (Rajasthan) 342 003



Website: www.cazri.res.in, Email: director@cazri.res.in Phone No. 0291 - 2786584(Dir.)/2786485(CAO)/2785981(AO) FAX: 0291 - 2788706(Dir.)/2786498(PME)

### 

**Sub:** Quotation for Water supply and Sanitary work with Putty, Distempering & Painting work at Bakery Unit (Phase-I), CAZRI, Jodhpur.

Dear Sir(s),

You are requested to kindly quote your lowest rates keeping in view the following conditions in respect of the articles indicated overleaf/as per statement enclosed (Schedule to Tender).

- 1. No advance payment will be made. However, the payment is normally made within 30 days from the date of receipt of Bill for execution the work **in good condition as per order**.
- 2. The quantity proposed in the quotation may be increased or decreased at the discretion of the authority while placing the order
- 3. Quotation not found according to specification will be rejected/not considered.
- 4. The firm should also supply a copy of the authorized dealership certificate of the item, if applicable
- 5. Quotation should remain valid for 3 months from the date of quotation.
- 6. No. Form 'C' & 'D' for sales tax will be issued. Payment will be made at full rate, if applicable. However, the firm is required to produce the valid sales tax Registration No. The firm should also indicate PAN/TIN as per Income Tax Rules.
- 7. The Rates **should be clearly indicated in figure as well as in words**. While quoting the rates, it may be clearly indicated whether the items are inclusive or exclusive of ST, CST etc. in terms of percentage or in absolute term.
- 8. Works will have to be completed normally within 30 days from the date of issue of work order or as mentioned in the supply order unless such extension is allowed by the Institute **failing which suitable penalty as indicated in the work order will be imposed.**
- 9. Director, CAZRI, Jodhpur reserves the right to accept or reject any or all the quotation without assigning any reason.
- 10. All bids must be accompanied by a bid security / **EMD of Rs. 4000/-** of the estimated value of the cost, in the form of a Demand Draft of a scheduled commercial bank in India, in favour of **ICAR Unit-CAZRI**, **Jodhpur.** Without EMD quotation will not be considered.
- 11. The firm awarded the contract may/will have to furnish a performance security in the form of Bank Guarantee as per the proforma to be supplied along with work order or FDR pledged to "ICAR Unit CAZRI, Jodhpur" from a scheduled Commercial Banks or it may be deducted from bills for an amount which may vary from 5% to 10% of the value of the contract at the discretion of Director, which should remain valid for six months.
- 12. The quotation may be sent to the office by courier/Registered Post/Speed Post in sealed cover super scribed with "Water supply and Sanitary work with Putty, Distempering & Painting work at Bakery Unit (Phase- I ), CAZRI, Jodhpur."
- 13. **The quotation** must be reached to this Office on or before **09/01/2015** upto **03.00 PM** failing which it will not be considered. The quotation should be dropped in the Tender Box placed in the Adm.V.

Yours faithfully,



# भा. कृ. अनु. प. — केन्द्रीय शुष्क क्षेत्र अनुसंधान संस्थान ICAR - Central Arid Zone Research Institute जोधपुर (राजस्थान) 342 003/Jodhpur (Rajasthan) 342 003



Website: www.cazri.res.in, Email: director@cazri.res.in
Phone No. 0291 – 2786584(Dir.)/2786485(CAO)/2785981(AO) FAX: 0291 – 2788706(Dir.)/2786498(PME)

#### निविदा प्रपत्र

#### (इस फार्म को निविदा प्रपत्र के साथ जमा कराना आवश्यक है)

निदेशक, केन्द्रीय शुष्क क्षेत्र अनुसंधान संस्थान, जोधपुर निम्नलिखित कार्य के लिए सीमित मोहरबन्द निविदाये आमंत्रित करते है

1.	कार्य का नाम	: Water supply and Sanitary work with Putty, Distempering &						
		Painting work at Bakery Unit (Phase – I), CAZRI, Jodhpur.						
2.	निविदादाता फर्म का नाम/पूर्ण पता	;						
3.	टेलिफोन / मोबाइल नम्बर	÷						
4.	निविदादाता फर्म का	: PAN No						
		: TIN No						
5.	बैंक का विवरण	ः बैंक का नाम						
		ः पता						
		: बैंक का IFS Code :						
		ः बैंक का खाता नम्बर ः						
6.	निविदा प्रपत्र की कीमत	ः रू. शून्य						
7.	धरोहर (बयाना) राशि	: ক্ত. 4000/- Demand Draft/Pay Order/Banker Cheque						
		ICAR Unit CAZRI, Jodhpur के पक्ष में देय हो ।						
8.	कार्य पूर्ण करने की अवधि	: एक माह						
9.	निविदा जमा कराने की अंतिम तिथि	: 09/01/2015 at 3.00 PM						
10.	निविदा कार्य की विस्तृत सूचना काज	री की बेवसाईट <u>http://www.cazri.res.in</u> पर देखी जा सकती है।						
11.	निविदा प्रपत्र काजरी, जोधपुर की वेब	साईट से भी डाउन लोड किये जा सकते है।						

निविदादाता के मोहर सहित हस्ताक्षर

## ${\color{red} \underline{Name\ of\ Work:}} \ \ Water\ supply\ and\ Sanitary\ work\ with\ Putty,\ Distempering\ \&\ Painting\ work\ at\ Bakery\ Unit\ (Phase-I\ ),\ CAZRI\ ,\ Jodhpur$

S.No.	Descriptions	<b>Quntity/unit</b>	Rate	Amount
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.			
	1:4:8 or leaner mix	1 cum	@	
	CEMENT CONCRETE (CAST – IN- SITU)			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:  1:2:4 (1 cement : 2 coarse sand : 4 graded stone			
	aggregate 20 mm nominal size)	0.3 cum	@	
3	1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)	1 cum	@	
	Brick work with F.P.S. bricks of class designation 75 in foundation and plinth in:			
4	Cement mortar 1:6 (1 cement : 6 coarse sand)	0.5 cum	@	
	CEMENT PLASTER (IN COARSE SAND)			
5	12 mm cement plaster of mix :			
	1:6 (1 cement: 6 coarse sand)	6 Sqm	@	
6	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors:			
	100 mm inlet and 100 mm outlet			
	Sand Cast Iron S&S as per IS: 1729.	1 Each	@	
	100 mm inlet and 75 mm outlet			
	Sand Cast Iron S&S as per IS: 1729.	1 Each	@	
	Providing and fixing single unequal plain junction of required degree :			
	100x100x75 mm			
7	Sand cast iron S&S as per IS - 1729	2 Each	@	
	Providing and fixing soil, waste and vent pipes:			
8	100 mm dia.			
	Sand cast iron S&S pipe as per IS: 1729.	2 Meter	@	
	75 mm dia.			
	Sand cast iron S&S pipe as per IS: 1729.	4 Meter	@	
	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete.			
9	Semi rigid pipe			
	40 mm dia	4 Each	@	

S.No.	Descriptions	Quntity/unit	Rate	Amount
10	Providing and fixing white vitreous china laboratory sink with C.I. brackets, C.P. brass chain with rubber plug 40mm C.P brass waste and 40mm C.P. brass trap with necessary C.P. brass unions complete including painting of fittings and brackets, cutting and making good the wall wherever required:			
	Size 600x450x200mm	2 Each	@	
	STONE WARE PIPES AND FITTINGS			
11	Providing, laying and jointing glazed stoneware pipes grade 'A' with stiff mixture of cement mortar in the proportion of 1:1 (1 cement : 1 fine sand) including testing of joints etc. complete :			
	150 mm diameter	18 Meter	@	
12	Providing and laying cement concrete 1:5:10 (1 cement: 5 coarse sand: 10 graded stone aggregate 40 mm nominal size) up to haunches of S.W. pipes including bed concrete as per standard design:			
	150 mm diameter S.W. pipe	18 Meter	@	
13	Providing and fixing square-mouth S.W. gully trap grade 'A' complete with C.I. grating brick masonry chamber with water tight C.I. cover with frame of 300 x300 mm size (inside) the weight of cover to be not less than 4.50 kg and frame to be not less than 2.70 kg as per standard design:			
	100x100 mm size P type			
	With F.P.S. Bricks class designation 75	2 Each	@	
14	Constructing brick masonry chamber for underground C.I. inspection chamber and bends with 75 class designation bricks in cement mortar 1:4 (1 cement : 4 coarse sand) C.I. cover with frame (light duty) 455x610 mm internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23 kg and weight of frame 15 kg) R.C.C. top slab with 1:2:4 mix (1 cement :2 coarse sand : 4 graded stone aggregate 20 mm nominal size) foundation concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size), inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished smooth with a floating coat of neat cement on walls and bed concrete etc. complete as per standard design:			
	Inside dimensions 455x610 mm and 45 cm deep for single pipe line :			
	With F.P.S. bricks	3 Each	@	
15	Making soak pit 2.5 m diameter 3.0 metre deep with 45 x 45 cm dry brick honey comb shaft with bricks of class designation 75 and S.W. drain pipe 100 mm diameter, 1.8 m long complete as per standard design.			

S.No.	Descriptions	Quntity/unit	Rate	Amount
	With F.P.S. bricks	1 Each	@	
	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc.		w	
	EXTERNAL WORK			
16	25 mm dia. nominal bore	40 Meter	@	
17	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete:			
	25 to 40 mm nominal bore	4 Each	@	
18	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, including cutting and making good the walls etc.			
	INTERNAL WORK – EXPOSED ON WALL.			
	15 mm dia. nominal bore	5 Meter	@	
	20 mm dia. nominal bore	15 Meter	@	
	25 mm dia. nominal bore	3 Meter	@	
19	Providing and fixing brass bib cock of approved quality:			
	15 mm nominal bore	4 Each	@	
20	18.17 Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end):			
	25 mm nominal bore	2 Each	@	
21	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete:			
21	15 mm nominal bore	1 Each	@	
	20 mm nominal bore	1 Each	@	
	Providing and fixing uplasticised PVC connection pipe with brass unions :			
	30 cm length 15 mm nominal bore			
	Steel work welded in built up sections/ framed	5 Each	@	
22	work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.			
	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	300 Kg	@	
23	Providing and fixing G.I. Union in existing G.I. pipe line, cutting and threading the pipe and making long screws including excavation, refilling the earth or cutting of wall and making good the same complete wherever required:			
	15 mm nominal bore.	2 Each	@	
	20 mm nominal bore.	2 Each	@	

S.No.	Descriptions	Quntity/unit	Rate	Amount
24	Providing and fixing brass stop cock of approved quality:			
	15 mm nominal bore	2 Each	@	
	20 mm nominal bore	2 Each	@	
25	Making connection of drain or sewer line with existing manhole including breaking into and making good the walls, floors with cement concrete 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) cement plastered on both sides with cement mortar 1:3 (1 cement : 3 coarse sand) finished with a floating coat of neat cement and making necessary channels for the drain etc. complete :			
	For pipes 100 to 230 mm diameter	6 Each	@	
26	Providing and fixing PTMT soap Dish Holder having length of 138mm, breadth 102mm, height of 75mm with concealed fitting arrangements. Weighing not less than 106 gms.	4 Each	@	
27	P & F PVC Storage Tank (IS:12701 marked indicating the BIS license No.) of approved make with cover, 25 mm dia 1 M long G.I. over-flow pipe & 25 Cm. long wash out pipe with plug & socket, including making connection etc. complete of approved design.			
	1000 litres capacity.	1 Each	@	
28	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade:			
	Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture.	70 Sqm	@	
29	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade			
	New work (two or more coats) over and including priming coat with cement primer.	200 Sqm	@	
30	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade:			
	One or more coats on old work.	84.17 Sqm	@	
31	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	200 Sqm	@	
	TOTAL			

PAN NO	)	 	 	 	 	 	 	٠.	 	
TIN NO	`									