

CENTRAL ARID ZONE RESEARCH INSTITUTE
(INDIAN COUNCIL OF AGRICULTURAL RESEARCH)
Jodhpur(Raj.)342 003, Phone-0291-2786485

F. No. 8(10)/Ren. Roof. KVK Hostel/12-13/Adm-V

Dated: 2013

To,

M/s.....
.....
.....

Sub: Repair/Renovation of roof at KVK Hostel, CAZRI, Jodhpur.

Dear Sir(s),

You are requested to kindly quote your lowest rates keeping in view the following conditions in respect of the articles indicated overleaf/as per statement enclosed (Schedule to tender).

1. No advance payment will be made. However, the payment is normally made within 30 days from the date of receipt of Bill for execution the work **in good condition as per order.**
2. The quantity proposed in the quotation may be increased or decreased at the discretion of the authority while placing the order.
3. Quotation not found according to specification will be rejected/not considered.
4. The firm should also supply a copy of the authorized dealership certificate of the item, if applicable
5. Quotation should remain valid for 3 months from the date of quotation.
6. No. Form 'C' & 'D' for sales tax will be issued. Payment will be made at full rate, if applicable. However, the firm is required to produce the valid sales tax Registration No. The firm should also indicate PAN/TIN as per Income Tax Rules.
7. The Rates **should be clearly indicated in figure as well as in words.** While quoting the rates, it may be clearly indicated whether the items are inclusive or exclusive of ST, CST etc. in terms of percentage or in absolute term.
8. Works will have to be completed within stipulated period as per work order **failing which suitable penalty as indicated in the work order will be imposed.**
9. Director, CAZRI, Jodhpur reserves the right to accept or reject any or all the quotation without assigning any reason.
10. All bids must be accompanied by a bid security/**EMD of Rs. 8100/-** of the estimated value of the cost, in the form of a Demand Draft of a scheduled commercial bank in India, in favour of **ICAR Unit-CAZRI, Jodhpur.** Without EMD quotation will not be considered.
11. The firm awarded the contract may/will have to furnish a performance security in the form of Bank Guarantee as per the proforma to be supplied along with work order or FDR pledged to **"ICAR Unit - CAZRI, Jodhpur"** from a scheduled Commercial Banks or it may be deducted from bills for an amount which may vary from 5% to 10% of the value of the contract at the discretion of Director, which should remain valid for six months.
12. The quotation may be sent to the office by courier/Registered Post/Speed Post in sealed cover super scribed with **"Repair/Renovation of roof at KVK Hostel, CAZRI, Jodhpur."** **Due date 07/09/2013.**
13. **The quotation** must be reached to this Office on or before **07/09/2013to 3.00 PM** failing which it will not be considered. The quotation should be dropped in the Tender Box placed in the Adm.V .

Yours faithfully,

ASSISTANT ADMINISTRATIVE OFFICER (ADM.V)

Name of Work: Repair/Renovation of roof at KVK Hostel, CAZRI, Jodhpur.

S. No.	Description	Quantity	Rate to be quoted	Amount (Rs.)
1.	Demolishing lime concrete manually / by mechanical means and disposal of material within 50 meters lead as per direction of Engineer-in- charge	22 Cum	@...../Cum
2.	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 meter lead.	100 Sqm	@...../Sqm
CEMENT PLASTER (IN CARSE SAND)				
3.	20 mm cement plaster of mix : 1 : 6 (1 cement : 6 coarse sand)	100 Sqm	@...../Sqm
4.	Grading roof for water proofing treatment with Cement concrete 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	32 Cum	@...../Cum
5.	Providing and laying brick tiles of class designation 100 over mumty roofs grouted with cement mortar 1 : 3 (1 cement : 3 fine sand) mixed with 2% of integral water proofing compound by weight of cement, over a 12 mm layer of cement mortar 1 : 3 (1 cement : 3 fine sand) and finished neat : With F.P.S. brick tiles	425 Sqm	@...../Sqm
6.	Making khurras 45 X 45 cm with average minimum thickness of 5 cm cement concrete 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) over P.V.C. sheet 1m X 1m X 400 micron, finished with 12 mm cement plaster 1 : 3 (1 cement : 3 coarse sand) and a coat of neat cement rounding the edge sand making and finishing the outlet complete.	10 Nos.	@...../Each
7.	Providing and laying in suit five course water proofing treatment with APP (Atactic Polypropylene) modified Polymeric memberane over roof consisting of first coat of bitumen primer @ 0.40 Kg per Sqm, 2 nd & 4 th courses of bonding material @ 1.20 Kg/Sqm, which shall consist of blown type bitumen of grade 85/25 conforming to IS : 3 rd layer of roofing membrane APP modified Polymeric membrance 2.0 mm thick of 3.00 Kg/Sqm weight consisting of five layers prefabricated with centre core as 100 micron HMHDPE film sandwiched on both sides with polymeric mix and the polymeric mix is protected on both side with 20 micron HMHDPE film. 5 th , the top most layer shall be finished with brick tiles of class designation 100 grouted with cement mortar 1 : 3 (1 cement : 3 fine sand) mixed with 2% intergral water proofing compound by weight of cement over a 12 mm layer of cement mortar 1 : 3 (1 cement : 3 fine sand) and finished neat which shall be paid for separately.	425 Sqm	@...../Sqm

NOTE : The estimated items are based on CPWD DSR 2012.

PAN NO.

TIN No.

Signature and seal of tenderer